REPORT: TMCRETBW

Page 1 of 13

PROJECT ITEM:

1403346 METTER PRIMARY

STAGE: -

BENCHMARK: 40H

OP NUMBER: 10581855

CIRCUIT CIRCUIT TYPE	FROM REFERENCE	TO REFERENCE	FUNCTION VOLTAGE	#CABLES #CONDS		SIZE INSULATION GTH REMARKS/REVISION
1/DC-1	PANEL 1	SS. INDOOR DC CABINET	INSTALL	1	#10	600V PIPJ
	D-91-002	D-99-001		2		60
10/DC-1	PANEL 10	SS. INDOOR DC CABINET	INSTALL	1	#10	600V PIPJ
	D-96-002	D-99-001		2		60
10/DC-2	PANEL 10	SS. INDOOR DC CABINET	INSTALL	1	#10	600V PIPJ
	D-96-002	D-99-001		2		60
10/DC-3	PANEL 10	SS. INDOOR DC CABINET	INSTALL	1	#10	600V PIPJ
	D-96-002	D-99-001		2		60
10-1T/400R1	PANEL 10	PANEL 1T	INSTALL	1	#10	600V PIPJ
	D-96-002	D-97-002		4		35
10-1T/400R2	PANEL 10	PANEL 1T	INSTALL	1	#10	600V PIPJ
	D-96-002	D-97-002		4		35
10-1T/CAP1RN	PANEL 10	PANEL 1T	INSTALL	1	#10	600V PIPJ
	D-96-002	D-97-002		2		60
10-1T/PR	PANEL 10	PANEL 1T	INSTALL	1	#10	600V PIPJ
	D-96-002	D-97-002		4		35
10-400/COM1	PANEL 10	PCB 400	INSTALL	1	200M	FIBER OPTIC
	D-94-004	D-94-004		4		270
1-1T/152C1	PANEL 1	PANEL 1T	INSTALL	1	#10	600V PIPJ
	D-91-002	D-97-002		4		65
1-1T/152C2	PANEL 1	PANEL 1T	INSTALL	1	#10	600V PIPJ
	D-91-002	D-97-002		4		60
1-1T/152C3	PANEL 1	PANEL 1T	INSTALL	1	#10	600V PIPJ
	D-91-002	D-97-002		2		60
1-1T/152R1	PANEL 1	PANEL 1T	INSTALL	1	#10	600V PIPJ
	D-91-002	D-97-002		4		60
1-2/C1	PANEL 1	PANEL 2	INSTALL	1	#10	600V PIPJ
	D-91-002	D-92-002		2		25

GEORGIA POWER COMPANY

BILL OF WIRE

DATE: 1/24/2024 LISTED: ADDERLEY, KAYLA FACILITY ID: 15-635-BW REV 00

REPORT: TMCRETBW

Page 2 of 13

PROJECT ITEM:

1403346 METTER PRIMARY

GEORGIA POWER COMPANY
BILL OF WIRE

STAGE: -

BENCHMARK: 40H

OP NUMBER: 10581855

CIRCUIT CIRCUIT TYPE	FROM REFERENCE	TO REFERENCE	FUNCTION VOLTAGE	#CABLES #CONDS		ZE INSULATION TH REMARKS/REVISION
1-2/P11	PANEL 1	PANEL 2	INSTALL	1	#10	600V PIPJ
	D-91-002	D-92-002		4		30
142REG/COM1	PANEL 8	PCB 112142	INSTALL	1	#24	SHIELDED
	D-94-004	D-94-004		4		265
142REG-T.O./COM1	T.O. PANEL	PCB 112142	INSTALL	1	#24	SHIELDED
	D-94-004	D-94-004		4		265
152/AC	B4152	SS. INDOOR AC CABINET	INSTALL	1	#10	600V PIPJ
	XXXX	D-99-003		4		245
1-8/COM1	PANEL 1	PANEL 8	INSTALL	1	#24	SHIELDED
	D-94-004	D-94-004		4		60
1-8/SAL1	PANEL 1	PANEL 8	INSTALL	1	#10	600V PIPJ
	D-91-002	D-94-002		4		40
1-8/SDC	PANEL 1	PANEL 8	INSTALL	1	#10	600V PIPJ
	D-91-002	D-94-002		2		60
1-T.O./COM1	PANEL 1	T.O. PANEL	INSTALL	1	#24	SHIELDED
	D-94-004	D-94-004		4		60
1T-10/400C1	PANEL 1T	PANEL 10	INSTALL	1	#10	600V PIPJ
	D-97-002	D-96-002		4		35
1T-10/400C2	PANEL 1T	PANEL 10	INSTALL	1	#10	600V PIPJ
	D-97-002	D-96-002		4		35
1T-10/400C3	PANEL 1T	PANEL 10	INSTALL	1	#10	600V PIPJ
	D-97-002	D-96-002		4		35
1T-10/400C4	PANEL 1T	PANEL 10	INSTALL	1	#10	600V PIPJ
	D-97-002	D-96-002		4		35
1T-152/C1	PANEL 1T	B4152	INSTALL	1	#10	600V PIPJ
	D-97-002	XXXX		4		235
1T-152/C2	PANEL 1T	B4152	INSTALL	1	#10	600V PIPJ
	D-97-002	XXXX		4		235

DATE: 1/24/2024 LISTED: ADDERLEY, KAYLA FACILITY ID: 15-635-BW REV 00

REPORT: TMCRETBW

Page 3 of 13

PROJECT ITEM: 1403346

GEORGIA POWER COMPANY
BILL OF WIRE

STAGE: -

BENCHMARK: 40H

METTER PRIMARY

OP NUMBER: 10581855

CIRCUIT CIRCUIT TYPE	FROM REFERENCE	TO REFERENCE	FUNCTION VOLTAGE	#CABLES #CONDS	SIZI LENGTH	
1T-152/C3	PANEL 1T	B4152	INSTALL	1	#10	600V PIPJ
	D-97-002	XXXX		2	25	0
1T-152/C4	PANEL 1T	B4152	INSTALL	1	#10	600V PIPJ
	D-97-002	XXXX		2	23	0
1T-152/R1	PANEL 1T	B4152	INSTALL	1	#10	600V PIPJ
	D-97-002	XXXX		4	23	5
1T-152/R2	PANEL 1T	B4152	INSTALL	1	#10	600V PIPJ
	D-97-002	XXXX		4	23	5
1T-176/P11	PANEL 1T	B4176	INSTALL	1	#10	600V PIPJ
	D-97-002	XXXX		4	15	5
IT-2/152C1	PANEL 1T	PANEL 2	INSTALL	1	#10	600V PIPJ
	D-97-002	D-92-002		2	6	0
1T-2/746C4	PANEL 1T	PANEL 2	INSTALL	1	#10	600V PIPJ
	D-97-002	D-92-002		2	6	0
1T-2/C1	PANEL 1T	PANEL 2	INSTALL	1	#10	600V PIPJ
	D-97-002	D-92-002		2	6	0
1T-2/C2	PANEL 1T	PANEL 2	INSTALL	1	#10	600V PIPJ
	D-97-002	D-92-002		4	6	0
1T-2/C3	PANEL 1T	PANEL 9	INSTALL	1	#10	600V PIPJ
	D-97-002	D-92-002		2	6	0
1T-400/C1	PANEL 1T	112400	INSTALL	1	#10	600V PIPJ
	D-97-002	XXXX		4	22	0
1T-400/C2	PANEL 1T	112400	INSTALL	1	#10	600V PIPJ
	D-97-002	XXXX		4	22	0
1T-400/C3	PANEL 1T	112400	INSTALL	1	#10	600V PIPJ
	D-97-002	XXXX		4	22	0
1T-400/C4	PANEL 1T	112400	INSTALL	1	#10	600V PIPJ
	D-97-002	XXXX		4	22	

DATE: 1/24/2024 LISTED: ADDERLEY, KAYLA FACILITY ID: 15-635-BW REV 00